

TOWN OF BEDFORD



Public Information Meeting Agenda Bedford Center Road Paving and Shoulder Widening

Introduction – Supervisor Lee V.A. Roberts

Project Summary – Kevin Winn

- The County of Westchester and Town of Bedford are planning pavement replacement and shoulder widening on Main Street and Bedford Center Road.
 - 2006 Intermunicipal Agreement - The construction contract will be issued and administered by Westchester County. Maintenance responsibility of the road will be transferred to the Town.
 - Pavement replacement will occur from Adams Street to Succabone Road.
 - In accordance with the strategy identified in the Town's Comprehensive Plan, the project design includes an expanded paved shoulder for use by bicyclists and other non-vehicle uses.
 - Shoulder widening will occur from Springhurst Road to Route 22. Shoulders are planned to be widened from an existing average of approximately two feet to a new dimension of four feet.
 - Several portion of the road with drainage problems will be improved.
 - Narrows, hill along Main Street
 - The County has identified six trees that will be removed due to their deteriorated condition and/or proximity to the work.

Project Details - Westchester County and Berger Lehman Associates

- Design details
 - Difference between widened outside lane, paved shoulder, bicycle lane, and multi-use path
 - 4' paved shoulder
 - Sidewalk and curb replacement
 - Guiderail replacement
 - Mountable colored concrete curb where terrain slopes up from shoulder
 - Drainage improvements
 - Correct flooding problem at Narrows
 - Eliminate surfacing water on Main Street by Springhurst
- County has complied with SEQRA and stormwater regulatory requirements.

Questions and Answers